

2010 Parfet Estates Berm Storm Sewer Project
ADDENDUM #3
March 2, 2010

1.01 GENERAL

The following changes, additions, and/or deletions are, by issuance of this Addendum, made a part of the Project Manual for 2010 Parfet Estates Berm Storm Sewer for The City of Golden, as if originally contained therein. Execution of the acknowledgement of receipt shall be the bidder's acceptance of the conditions herein set forth. All Bidders shall acknowledge receipt of this addendum on the Bid Form. Failure to do so will result in rejection of the Bid.

1.02 MODIFICATIONS TO SPECIFICATIONS

1. SECTION 00 41 43 BID FORM

- Schedule A: Has been re-arranged for clarification.
- Schedule B: Has been removed from the Bid Form.

The Contractor shall use the attached **Addendum #3 – 00 41 43 Bid Form** for the bid submittal. Use of the original bid form shall be considered non-responsive.

2. SECTION 01085 MEASUREMENT AND PAYMENT

- Add the following to Part 1.17 Storm Sewers:

“E. A unit price shall cover the entire cost of each additional two (2) feet of vertical depth in excess of ten (10) feet, including trenching and backfill. Pipe and bedding shall not be considered as part of the cost for additional depth.”

3. SECTION 02210 MANHOLES

- Change Section 1.4 Alternatives to read:

“A. All manhole bases shall be cast-in-place. See SECTION 02050 – CAST-IN-PLACE CONCRETE for concrete specifications.”

- Change “(SANITARY SEWER)” in Section 2.5 Ring and Cover, Part B.6. to read “(STORM SEWER)”

- Add the following to Section 2.5 Ring and Cover, Part B:

“7. All manhole rings and covers shall be bolt down.”

1.03 MODIFICATIONS TO DRAWINGS

1. Sheet 2

- The Welch Ditch Re-Grading is removed from the project.

1.04

CLARIFICATIONS

1. Surveying and alignment staking shall be considered a subsidiary obligation of CONTRACTOR and all costs in connection therewith shall be included in the prices bid. CONTRACTOR should expect to stake the project twice before construction, as prior to any construction, the staked alignment shall be walked with the CITY and ENGINEER and adjustments made at the discretion of the CITY and ENGINEER.
2. A digital CAD file will be provided to the Successful Bidder to use as the basis for staking.
3. The storm piping and manholes are a standard line item for up to ten (10) feet of bury. Additional vertical depth shall be paid for per the line items on the bid form. The additional depth does not include pipe or bedding.
4. All manholes shall be cast-in-place and at two (2) locations shall have additional depth in the base to act as anchoring.
5. The CITY requests minimal disturbance for the entire project.
6. Access to the site is limited to Parfet Estates Drive.
7. The CITY will provide all structural fill material, if needed, for the manhole bases and stilling basin.
8. Bedding for the HDPE pipe is the responsibility of the CONTRACTOR.
9. If additional permits are required for any work within the project scope, the contractor will be reimbursed with associated costs.
10. Potholing information is available from the CITY.
11. Bedding is not anticipated to be required for the RCP pipe.
12. The RCP specification is from Urban Drainage. Specific requirements may be waived if all requirements of Part 1.1 of Section 02095 are met.
13. Compaction required for this project shall be 90%.
14. The Project is covered under an existing SWMP permit.
15. The primary contact for questions relating to project design is Ward Mahanke, TST Engineers, 303-792-0557.
16. The Owner's primary contact for process and contract related questions is Jeremy Reichert, 303-384-8154.

City of Golden
Public Works Department
Vince Auriemma, P.E.
City Engineer

--End of Addendum #3--